



**TEMPORARY PUMPING NOTES:**  
CONTRACTOR TO PROVIDE TEMPORARY PUMP AND FORCE MAIN AS SHOWN ON PLANS. THE TEMPORARY PUMP SHALL BE ABLE TO HANDLE A MINIMUM OF 800 GPM AT 67 FT TDH. REDUNDANT PUMPING EQUIPMENT REQUIRED TO REMAIN ON-SITE UNTIL THE COMMISSIONING REQUIREMENTS HAVE BEEN SATISFIED. TEMPORARY PUMPING SHALL INCLUDE FLOAT SYSTEM TO AUTOMATICALLY TURN THE PUMP ON AND OFF BASED ON WETWELL LEVEL. CONTRACTOR SHALL NOT ALLOW SEWAGE LEVEL IN WET WELL TO RISE ABOVE AN ELEVATION OF 16.0' (OR 7.33' ABOVE THE WETWELL FLOOR SLAB).


**UNIVERSITY OF WASHINGTON**  
**SOUTH CAMPUS LIFT STATION**  
**IMPROVEMENTS - PROJECT NO. 2036683**  
**EXISTING SITE, TESC, AND BYPASS PUMPING PLAN**

[illegible]